OFFICE OF THE PRESIDENT, DISTRICT BOARD, BANGALORE.

Notification No. E. C. 97 of 39-40, dated 23rd November 1939.

Notice is hereby given that sealed tenders will be received at the Office of the President, District Board, Bangalore, up to 4 P.M. on the 9th December 1939, for constructing the Primary School Buildings at Seekote and Mallasandra Villages in Bangalore Taluk, Tippur Village in Dodballapur Taluk, and Urdu School Buildings at Sathnur and Harohalli Villages in Kankanhalli Taluk. An approximate ofestimate quantities for each of the five schools is given hereunder. These quantities are not guaranteed. The work should be completed by the end of 30th April 1940.

2. The plans, detailed estimate and conditions may be seen at the District Board Office, Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms (for each school separately) which may be obtained from the President, District Board, Bangalore. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing the Primary School Buildings at Seekote, Mallasandra, Tippur, Santhur and Harohalli Villages," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the President, District Board, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual Contract Bond, in default of which his tender will be considered cancelled and his earnest money be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the District Board Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per scheduled rates of the Department or those fixed by the President, District Board, after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the President, District Board, Bangalore, will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation at so much percentage less or more than the estimated rate will not be accepted.

Abstract estimate for constructing Primary School Buildings at Seekote, Mallasandra in Bangalore Taluk.

Item No.	Name of work	Unit	Quantity	Per	Rate to be given
		Quantity for each school			Rs. a. p.
1	Earthwork excavating foundation ...	C.yd.	22		
2	Burnt stone jelly concrete with Chunam ...	C.ft.	200		
3	Burnt stone in mortar foundation ...	,,	321		
4	Burnt stone in mortar basement ...	,,	183		
5	Burnt brick in mortar	,,	735		
6	Burnt stone slab 6″ thick dressed and fixed in mortar.	S.ft.	213		
7	Burnt stone pillars 2 line dressed including cutting grooves.	No.	6		
8	Teakwood door with panelled shutters including 2 coats of painting.	S.ft.	32		
9	Teakwood windows including iron bars panelled shutters and complete.	,,	87		
10	Roofing with Madras Terrace with plastering, etc., complete.	Sqr.	3·88		
11	Flooring with Cudappah slabs over 3″ lime concrete including cement pointing.	,,	3·30		
12	Rolled steel joists including carting, lifting and hoisting.	Cwt.	2		

Item No.	Name of work	Unit	Quantity	Per	Rate to be given
13	Boxing steel joists with cement mortar	R.ft.	22		
14	S. M. Rails	,,	78		
15	Angle Iron patties fixing with bolts and nuts to rails.	Lump sum			
16	Masonry Pillars with size stones in cement mortar with bond stones and plastering complete as per design.	No.	4		
17	Teakwook wrought and put up including wood oiling.	C.ft.	45·56		
18	Reinforced Cement Concrete frames ...	S.ft	142		
19	Plastering with Chunam	Sqr.	16 45		
20	White washing	,,	16·45		
21	Water spouts	R.ft.	18		
22	Cement pointing	Sqr.	1·69		
23	Grape plants to be planted with manure, etc....	Lump sum			
24	Constructing Block cornice all round ...	R.ft.	83		
25	R. C. C. Tree guards	Lump sum			
26	Cement border all round in hall with 1" with red coating to a height of 1' to prevent damage to the walls by benches.	R.ft	74		
27	Parapet over roof with burnt brick in mortar including chunam plastering.	R.ft.	78½		

Abstract estimate for constructing Primary School Building at Tippur Village in Dodballapur Taluk.

1	Earthwork foundation	C.yd.	30		
2	Burnt stone jelly concrete	C.ft.	392		
3	Burnt size stone in clay foundation ...	,,	330		
4	Burnt size stone in clay basement ..	,,	137		
5	Burnt brick in clay	,,	547		
6	Burnt brick in mortar	,,	232		
7	Size stone in mortar. Pillars	,,	25		
8	Double joists for bressummer	Cwt.	2		
9	Burnt stone slabs sides dressed	S.ft.	184		
10	Reinforced cement concrete honey comb work as per design.	,,	112		
11	Boxing the double joists for bressummer ...	R.ft.	22		
12	Teakwood wrought and put up including wood oiling.	C.ft.	46·38		
13	Pucca terrace including mortar plastering complete.	Sqr.	3·88		
14	Parapet wall burnt brick in mortar including plastering.	R.ft.	78½		
15	Burnt brick in mortar block course ...	,,	83		
16	Teakwood windows with four shutters including iron bars and painting complete.	S.ft.	82½		
17	Teakwood door panelled shutters complete ...	,,	24		
18	Burnt stone pillars with two line dressing including cutting groves	No.	6		
19	Chunam plastering	Sqr.	17 03		
20	White washing	,,	17·03		
21	Flooring with 1½" thick cement concrete over 3" burnt stone jelly concrete and plastering with cement half inch thick mixed with red ochre and cut into squares smoothened.	,,	3·30		
22	Cement pointing	,,	1·27		
23	S. M. Rails over the pillars	R ft.	36		
24	Bamboos over rails and planting creepers ...	Lump sum			
25	Levelling ground	Lump sum			

Abstract estimate for constructing Urdu Primary School Building at Sathnur and Harohalli Villages in Kankanhalli Taluk.

Item No.	Name of work	Unit	Quantity	Per	Rate to be given
		Quantity for each school			Rs. a. p.
1	Earthwork excavating foundation ...	C.yd.	18		
2	Burnt stone in mortar foundation ...	C.ft.	487		
3	Do basement ...	,,	176		
4	Burnt brick in mortar ..	,,	725		
5	Burnt stone slabs 6" thick well dressed and fixed in mortar.	S.ft.	213		
6	Madras terrace including plastering, etc. ...	Sqr.	3·88		
7	Burnt stone pillars 3 line dressed including cutting grooves	No.	6		
8	Masonry pillars as per design ...	,,	4		
9	S. M. Rails including fixing ...	R.ft.	36		
10	Angle iron patties fixing with bolts and nuts.	Lump sum			
11	R. C. C. Trellis work ...	S.ft.	115		
12	Teakwood door with panelled shutters and painting complete.	,,	32		
13	Teakwook windows with iron bars panelled shutters and painting complete.	,,	87		
14	Plastering with chunam ...	Sqr.	16·45		
15	Flooring with Cudappah slabs over 3" lime concrete including cement pointing.	,,	3 30		
16	Cement pointing to basement ..	,,	1·69		
17	White washing ...	,,	16·45		
18	Grape plant to be planted with manure ...	Lump sum			
19	R. C. C. Tree guard ...	,,			
20	Teakwood wrought and put up including wood oiling.	C.ft.	45·56		
21	Steel joists for Bressummer including hoisting.	Cwt.	2		
22	Boxing steel joists with cement concrete ...	R.ft	22		
23	Parapet wall burnt brick in mortar coping and plastering complete.	,,	78½		
24	Constructing block cornice all round out side.	,,	83		
25	Zinc water spouts ...	,,	18		
26	Teakwood beading all round wall to prevent damage by benches including fixing.	,,	74		
27	Levelling ground .	Lump sum			

B. A. RAHMON,
President.

BANGALORE DISTRICT.

Notification No. C2 4004—38-39, *dated 12th November* 1939.

In virtue of the powers vested under Section 6(3)(*d*) and Section 15 of the Minor Municipalities Act and Rules framed thereunder, the following gentlemen are nominated as Municipal Councillors of Nelamangala Minor Municipal Council in the existing vacancies :—

Messrs.—
1 Muddananjunda Setty
2 N. Nanjunda Setty
3 C. Lakshminarasimhiah
4 N. Keshava Murthy
5 Hassauzamankhan

Messrs.—
6 Abid Hussain Sheriff
7 N C. Pappiah
8 N. C Muniappa
9 M. Hanumanthiah